

Maxson Painting

Quality service at a value

CA LIC. # 607049



September 13, 2006

General Contractor Enterprises, Inc.
P.O. Box 1234
Ventura, CA 93003

Re: Exterior Painting of Your Next Project

I propose to furnish all materials and labor necessary to complete the following:

1. Treat mildew and pressure wash exterior of building to remove dirt and mildew.
2. Hand scrape, hand sand and power sand all surfaces as needed to remove loose and failing material. Our power sanders use specially designed material removal discs, these discs remove all loose and failing material yet do not damage wood surfaces.
3. Apply oil primer to all raw wood. Includes a full coat of primer to inside of wood siding enclosure and patio cover.
4. Fully caulk and patch all surfaces as needed using only flexible elastomeric products. These products move with the surfaces they are applied to, therefore they last longer than ordinary products.
5. Trench down 2-3 inches at base of stucco and apply UGL Drylock primer to all areas where moisture intrusion is evident.
6. Patch stucco using bonderizing stucco patch additive.
7. Prime gas meter, iron bars on front of building, roof access ladder and iron gate with industrial rust blocking primer as needed.
8. Apply two coats of quality 100% acrylic satin sheen house paint to siding, window trim, patio cover and siding. Satin sheen paints resist UV rays and moisture better than ordinary flat paints. Satin sheen paints have 20% side sheen.
9. Finish coat gas meter, iron bars on front of building, roof access ladder and iron gate with industrial rust blocking gloss enamel.
10. Apply two coats of quality 100% acrylic non-blocking semi-gloss enamel to painted doors.
11. Apply one coat of quality 100% acrylic flat paint to all stucco. Spray and back-roll method is to be used to insure full and complete coverage as well as proper touch up in the future.

*PMB 419 3875-a Telegraph Road, Ventura CA 93003 Phone / Fax (805) 644-0625
Email: maxsonpainting@sbcglobal.net*

12. Protect all surfaces not being painted.
13. Provide large color samples and assist in color selection as needed.
14. Provide properly labeled touch up paint for future use.
15. Work will require approximately nine to ten working days.
16. Remove all paint related materials.

All of the above work is to be completed in a workmanlike manner according to standard practices for the sum of \$_____. Payment of 20% due when work begins, balance due upon completion. Two-percent per month will be charged on overdue balances.

Any alteration or deviation from the above specifications involving extra cost of material or labor will be considered an extra charge over the sum mentioned above.

Thank you for the opportunity to be considered for your painting project. If you are in agreement with this proposal, please sign and return one copy of this proposal to our office for processing, retaining one copy for your records. If you have any questions please feel free to contact me at (805) 644-0625.

Respectfully Submitted:

Accepted:

George E. Maxson

George E. Maxson

Date: